

Rekapitulasi Perhitungan *Critical Path Method* (CPM)

ID	Aktivitas	Predecessor	Durasi (Hari)	ES (Hari)	EF (Hari)	LS (Hari)	LF (Hari)	TF (Hari)	Critical	Biaya (Rp. × 10 ⁶)
1	Pekerjaan Persiapan, Prasarana dan Penunjang	-	14	0	14	0	14	0	Yes	389,75
2	Pekerjaan Struktur	1	42	14	56	14	56	0	Yes	707,30
3	Pekerjaan Lift	2	32	56	88	56	88	0	Yes	193,91
4	Pekerjaan Koridor	3	36	88	124	88	124	0	Yes	1.273,27
5	Pekerjaan Canopy	4;8	30	124	154	124	154	0	Yes	750,23
6	Pekerjaan Walkway Cooling Tower	2	7	56	63	82	89	26	No	13,04
7	Pekerjaan Smoking Area	6	28	63	91	89	117	26	No	266,24
8	Pekerjaan Penggantian Pintu Besi	7	7	91	98	117	124	26	No	354,46
9	Pekerjaan Pagar Keliling	1	60	14	74	24	84	10	No	1.555,30
10	Pekerjaan Pagar Depan	9	21	74	95	84	105	10	No	184,72
11	Pekerjaan Pintu Pagar	10	7	95	102	105	112	10	No	112,51
12	Pekerjaan Pagar Besi	11	14	102	116	112	126	10	No	53,04
13	Pekerjaan Perbaikan Groundtank Solar	12;26	21	116	137	126	147	10	No	738,33
14	Pekerjaan Perbaikan Koridor MEP	13	14	137	151	147	161	10	No	92,83
15	Pekerjaan Perbaikan Jalan Aspal	14	7	151	158	161	168	10	No	130,91
16	Pekerjaan Arsitektur	2;6	14	63	77	102	116	39	No	81,28
17	Pekerjaan Penutup Tray Kabel	3;16	14	88	102	116	130	28	No	52,94
18	Pekerjaan Louvre Koridor	4;17	10	124	134	130	140	6	No	49,17
19	Pekerjaan Perapihan Kembali Koridor	18	14	134	148	140	154	6	No	15,13
20	Pekerjaan Pengecatan	19	14	148	162	154	168	6	No	211,45
21	Perbaikan Atap	1	42	14	56	44	86	30	No	800,22
22	Pekerjaan Plafond Area Trafo	21	14	56	70	86	100	30	No	64,92
23	Pekerjaan Covering Panel FO	22	7	70	77	100	107	30	No	45,85
24	Pekerjaan Green Wall	10;23	10	95	105	107	117	12	No	295,31
25	Pekerjaan Taman Dan Perbaikan Pos Keamanan	24	5	105	110	117	122	12	No	32,83
26	Pekerjaan Signage	25	4	110	114	122	126	12	No	34,09
27	MEP Area Bangunan Cooling Tower	2	14	56	70	120	134	64	No	138,83
28	MEP Area Pagar Keliling	9;27	10	74	84	134	144	60	No	172,27
29	MEP Area Bangunan Existing	4;28	10	124	134	144	154	20	No	418,64
30	MEP Area Canopy Entrance & Gerbang	5;29	14	154	168	154	168	0	Yes	117,91
31	Selesai	15;20;30	0	168	168	168	168	0	Yes	-
										9.346,66

Total biaya Langsung	9.346,66	× 10 ⁶
Biaya tidak langsung perhari	2,00	× 10 ⁶
Total Durasi Proyek	168	hari
Total biaya tidak langsung	336,00	× 10 ⁶
Total Biaya Proyek	9.682,66	× 10⁶